

le KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1965
8-30-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John C. Graves

Complete Address: 412 Union Center, Wichita, Kansas

Lease Name Dralle Well No. # 1

Location NW SW NE Sec. 9 Twp. 22 Rge. 14 (E) (W)W

County Stafford Total Depth 3920'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Graves Drilling Company, Inc.

Address: 412 Union Center, Wichita, Kansas License No.

Operation Completed: Hour 8:00PM Day 26th Month August Year 1965

The Above well was plugged as follows:

221' of 8 5/8" surface pipe, cement circulated with 220 sacks. Fluid
level in the hole was at 130'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 210', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Achie Elving
Well Plugging Supervisor

DATE 8/30/65

INV. NO. 1712-W