

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1967
10-25-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued October 9, 1967.

Operator's Full Name Petroleum, Inc.

Complete Address: R. R. # 2, Great Bend, Kansas 67530

Lease Name Strobel Well No. # A-1

Location SE SW NW Sec. 9 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3877'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 12:15 PM Day 23rd Month October Year 1967

The Above well was plugged as follows:

220' of 8 5/8" surface pipe, cemented with 175 sacks. 3876' of 5 1/2" long string,
cemented with 150 sacks. Plug back T. D. 3688'. Top perforation 3598'. Bottom
of the hole was sanded to 3550', and cemented with 5 sacks, through the dump
bailer, with cement from 3550' to 3510'. 2816' of 5 1/2" long string was recovered
from the hole. Hole was flowing with water, and was squeezed. 10 sacks of Gel-
Mud and 80 sacks of cement was pumped into the surface pipe, through an 8 5/8"
swage, to a pressure of 100 lbs., with cement from 240' to the base of the cellar.
This cementing was done by Glenn & Smith Casing Pulling Company.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE: 10/26/67
INV. NO. 6559-a