

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 11, 1967

Operator's Full Name Quality Oil Company

Complete Address: 6320 Jacqueline, Wichita, Kansas

Lease Name Strobel "B" Well No. # 1

Location C ^NW/2 NW SW Sec. 9 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3911'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:15PM Day 24th Month Jan. Year 1967

The Above well was plugged as follows:

243' of 8 5/8" surface pipe, cemented with 175 sacks. 3910' of 5 1/2" long
string, cemented with 150 sacks. This is an open hole. Bottom of the hole
was sanded to 3900', and cemented with 5 sacks, through the dump bailer.
2817' of 5 1/2" long string was recovered from the hole. Hole was flowing,
and a squeeze job was necessary. 10 sacks of Gel-Mud, and 80 sacks of
cement was pumped into the surface pipe, through an 8 5/8" swage, to a
pressure of 150 lbs., bringing the top of the cement to the base of the
cellar. A wiping plug was run between the Gel-Mud and the cement. This
cement was pumped by Knight Casing Pulling Company

I hereby certify that the above well was plugged as herein stated.

INVOICES

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/27/67
INV. NO. 4674-W