

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 11 1971
CONSERVATION DIVISION
Wichita, Kansas
11-11-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name E.K. Edmiston
Complete Address 801 1st Natl Bnk Bldg. Wichita, Ks
Lease Name Dudrey Well No. 1
Location SE/SE/NW Sec. 21 Twp. 22 Rge. 13 (E) (W) W
County Stafford Total Depth 3839
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Rockhold Engineering Inc.
Address Box 698 Great Bend, Ks License No. 670
Operation Completed: Hour 11:00 AM Day 9 Month 11 Year 1971

The above well was plugged as follows:

250 ft 8 5/8 surface pipe cemented circulated. 3837 ft 5 1/2 long string
cemented with 600 gals. latex. Top perf. 3615 ft. Push plug to
3570 ft. Sand back to 3540 ft, 5 sacks cement with bailer. Pulled
1820 ft 5 1/2. Pump 2 sacks hulls, 15 sacks gel, 100 sacks cement to
surface.

Pumped by Sun Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11-11-71

INV. NO. 4603-W