

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford

County, Sec. 22 Twp. 22 Rge. (E) 13 (W)

Location as "NE/CNW%SW%" or footage from lines C NE SW SW

Lease Owner Cooperative Refinery Ass'n.

Lease Name Witt "C" Well No. 1

Office Address Box 765 Great Bend, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed May 11 19 57

Application for plugging filed March 12 19 59

Application for plugging approved March 13 19 59


Plugging commenced May 2 19 59

Plugging completed May 15 19 59

Reason for abandonment of well or producing formation Non commercial production SWD

If a producing well is abandoned, date of last production January 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3833 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	306	-0-
				5 1/2	3828 1/2	2829.75'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with chat to 3570'. Dumped 5 sx. cement mudded hole to 280', 10 ft. rock bridge, dumped 20 sx. cement, mudded to 40', 10 ft. rock bridge, dumped 10 sx. cement. Well complete.

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1959

CONSERVATION DIVISION
Wichita, Kansas

5-26-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wilson, Inc.

Address Stafford, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Jim Robinson

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson

Box 765 Gt. Bend, Ks.

(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of May, 19 59

My commission expires Sept. 24, 1960

Yvonne Adams

Notary Public.

PLUGGING
FILE SEC 221-22 R-124
BOOK PAGE 81 LINE 16

15. 185-00713-0000

W. H. Lease - Geology
~~Original~~ **COPY**

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company **COOPERATIVE REFINERY ASSOCIATION &**
Firm **Witt "C"** No. 1 BIRMINGHAM-BARTLETT

SEC. 22 T. 22 R. 13W
NE SW SW

Total Depth. 3833½'
Comm. 4-29-57 Comp. 5-11-57
Shot or Treated.
Contractor. Birmingham-Bartlett
Issued. 9-7-57

County Stafford
KANSAS



CASING:

8 5/8" 306' cem w/200 sz
5 1/2" 3828½' cem w/75 sz

Elevation. 1896' DF

Production. 29 BOPD

Figures indicate Bottom of Formations.

surface clay, sand	225
shale, shells	260
red shale, shells	305
red bed and shells	748
anhydrite	776
shale and shells	1310
shale	1540
lime and shale	2455
shale, lime streaks	2680
lime and shale	2880
lime	3230
lime and shale	3320
sandy shale	3400
brown lime	3406
lime and shale	3425
lime	3695
Conglomerate	3715
Viola chert	3740
chert and shale	3785
Simpson shale	3827
Arbuckle lime	3833½ RTD
Total Depth	

TOPS: SCOUT	
Heebner	3269
Brown Lime	3401
Lansing	3420
Conglomerate	3695
Viola	3715
Simpson	3767
Arbuckle	3827

RECEIVED
APR 13 1963
INGERSOLL OIL CO.