

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Corby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,078-0000

LEASE NAME DUNN

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1620 Ft. from S Section Line

4520 Ft. from E Section Line

SEC. 22 TWP. 22 RGE. 13 ~~Cor~~ (W)

COUNTY STAFFORD

LEASE OPERATOR KANSAS PETROLEUM INC.

ADDRESS 225 NORTH MARKET #310 WICHITA, KS. 67202

PHONE#(316) 267-2266 OPERATORS LICENSE NO. 5023

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 9-20-84

Plugging Commenced 2-3-94

Plugging Completed 2-4-94

The plugging proposal was approved on 12-10-1993 (date)

by STEVE DURANT (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation KANSAS CITY Depth to Top 3442 Bottom 3796 T.D. 3824

Show depth and thickness of all water, oil and gas formations. . .

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
ARBUCKLE	OIL & WATER	3828	3833	8 5/8	753	0
SIMPSON	OIL & WATER	3768	3798	5 1/2	3832	1556', 36 JTS. OF CEMENT
LANSING KC	OIL & WATER	3418	3645			STATE CORP. ACOB CORPORATION

Describe in detail the manner in which the well was plugged, indicating where the mud/cement was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

2-3-94: RIGGED UP, DUMPED 2 SX OF CEMENT DOWN HOLE, SHUT DOWN.

2-4-94: SHOT OFF CASING AT 2535, DID NOT COME LOOSE, CUT AGAIN AT 2200', CUT AGAIN AT 1556',

CASING CAME LOOSE, PULLED 36 JTS OF 5 1/2" CASING. RIGGED DOWN AND MOVED OUT. PRATT WELL SERVICE

NOT ON LOCATION DURING TOP HOLE PLUG.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KANSAS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: KANSAS PETROLEUM, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY

PLUGGING CONTRACTOR.
(Employee of ~~Operator~~ or ~~Operator~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Pratt, Inc.



SUBSCRIBED AND SWORN TO before me this 9th day of February, 19 94

My Commission Expires: February 6, 1997

Notary Public

15-185-22078-0000

Dresser Atlas

LATEROLOG

DRESSER

GAMMA RAY

NEUTRON

FILE NO.

Company KANSAS PETROLEUM, INC.

API NO.

Well DUNN NO. 1 15-185-22,078

1518522078

Field HAHN EAST EXT.County STAFFORD State KANSAS*Final
Print*

Location:

100' E, C-S/2-NW-SW

OTHER SERVICES

CALIPER

Sec 22 Twp 22S Rge 13WPERMANENT DATUM GROUND LEVEL ELEV. 1894LOGGING MEASURED FROM K.B. 8 FT. ABOVE P.D.DRILLING MEASURED FROM KELLY BUSHING

ELEVATIONS

KB 1902

DF

GL 1894

DATE	09/10/84	
RUN	1	
SERVICE ORDER	56373	
DEPTH-DRILLER	3833	
DEPTH-LOGGER	3827	
BOTTOM LOGGED INTERVAL	3826	
TOP LOGGED INTERVAL	40	
CASING - DRILLER	8 5/8	8 753
CASING - LOGGER	755	
BIT SIZE	7 7/8	
TYPE FLUID IN HOLE	STARCH	
DENSITY AND VISCOSITY	10.0	52
PH AND FLUID LOSS	NA	10.2
SOURCE OF SAMPLE	FLOWLINE	
RM AT MEAS. TEMP.	.076	82
RMF AT MEAS. TEMP.	.057	82
RMC AT MEAS. TEMP.	.095	82
SOURCE OF RMF / RMC	M	M
RM AT BHT	.055	113
TIME SINCE CIRCULATION	2 HRS.	
MAX. REC. TEMP. DEG. F	113	
EQUIP. NO. / LOC.	HL 6355	GREAT BEND
RECORDED BY	DIRK BECKER	
WITNESSED BY	WILLIAM SHEPARD	

RECEIVED
STATE CORPORATION COMMISSION
DEC 01 1993
KANSAS CONSERVATION DIVISION
Wichita, Kansas