


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Reno County. Sec. 18 Twp. 22 Rge. 9 (E) W (W)
Location as "NE/CNW3SW4" or footage from lines NW NE NE SE
Lease Owner McAdams Pipe & Supply Co.
Lease Name Homer Drake Well No. # 1
Office Address P. O. Drawer 960 ; Bristow, Oklahoma 74010
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed October 19 71
Application for plugging approved October 19 71
Plugging commenced October 19 19 71
Plugging completed October 21 19 71
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	211	None
				5 1/2"	3669	1550

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

October 19, 1971 Plugged off bottom. Dumped sand to 3600'. Mixed and dumped 5 sx of cement to 3560'.
October 21, 1971 Plugged off top. Allied Cementing Co. mixed and pumped down 8 5/8" surface casing ; 3 sx of hulls, 20 sx of gel and 75 sx of cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 11 1971
CONSERVATION DIVISION
Wichita, Kansas
11-11-71

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF Oklahoma, COUNTY OF Creek, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature]
(Address) Bristow, Oklahoma

SUBSCRIBED AND SWORN to before me this 5th day of September, 1971
My commission expires September 23, 1975
[Signature] Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-155-00080-0000


COPY

Company. THE GLOBE OIL & REFINING CO.
Farm. Homer Drake "B" No. 1

SEC. 18 T. 22 R. 9W
App. 60' N of NW NE SE

Total Depth. 3670'
Comm. 10-17-58 Comp. 10-30-58
Shot or Treated.
Contractor. Group Exploration Co.
Issued. 12-20-58

County Reno KANSAS



Elevation. 1740' RB

CASINO:
8 5/8" 211' cem w/200 sx.
5 1/2" 3679' cem w/100 sx.

Production. 140 bbls. oil plus
82 bbls. water (37%)
Physical

Figures Indicate Bottom of Formations.

clay	26
sand & shale	220
red bed & shale	340
Anhydrite	365
red bed & shale	740
shale	1250
shale & lime	1450
lime	1950
lime & shale	2170
shale	2395
shale & lime	2645
lime	3050
shale & sand	3090
lime	3395
lime & shale	3625
sand	3645
shale	3660
Simpson	3670 RTD
Total Depth	

TOPS:	
Topeka	2636
Heebner	2931
Brown Lime	3077
Lansing	3106
Conglomerate	3440
Kinderhook	3454
Maquoketa	3500
Viola	3524
Simpson Shale	3621
Simpson Sand	3625
Base Simpson Sand	3642
RTD	3670
Schlumberger TD	3668

11-5-58 Perforated w/2 bullets and
2 super dyna jets per foot from
3625-3635'.

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1971
CONSERVATION DIVISION
Wichita, Kansas