


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 24 Twp 22 Rge 14 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NW SW
Lease Owner Anschutz Drilling Company, Inc.
Lease Name Smith Well No. 4
Office Address 709 Union Nat'l Bk Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-8-19 50
Application for plugging filed via telephone 5-8-19 50
Application for plugging approved via telephone 5-8-19 50
Plugging commenced 5-8-19 50
Plugging completed 5-8-19 50
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3801 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	325'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 375' with 15 sacks cement, filled hole to 30' with heavy mud, set plug at 30' with 8 sacks cement

5-18-50

MAY 18 1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anschutz Drilling Company, Inc.
Address 709 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
H. R. Jensen (employee of owner) or (owner or operator) of the above-described well,


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Jensen
709 Union Nat'l Bk Bldg., Wichita, Kans.
May 16, 1950
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of May, 1950

My commission expires September 12, 1953

March Dyer
Notary Public.



ANSCHUTZ DRILLING COMPANY, INC.

Smith #4 SE NW SW 24-22-14
Stafford County, Kansas

COMMENCED: 4-27-50
COMPLETED: 5-8-50

0	360	Sand and shale
360	815	Red bed and shells
815	835	Anhydrite
835	1220	Shale and shells
1220	1590	Shale and shells
1590	1625	Shale and shells
1625	1690	Shale and lime
1690	1785	Lime
1745	1880	Lime
1880	2005	Lime
2005	2130	Lime
2130	2210	Lime
2210	2390	Lime and shale
2390	2540	Lime and shale
2540	2650	Shale and lime
2650	2850	Lime and shale
2850	2950	Lime and shale
2950	3025	Lime
3025	3125	Lime
3125	3200	Lime
3200	3295	Lime
3295	3385	Lime
3385	3446	Lime
3446	3505	Lime
3505	3565	Lime
3565	3600	Lime
3600	3605	Lime
3605	3675	Lime
3675	3730	Lime
3730	3738	Lime
3738	3770	Congl
3770	3801	Lime
3801		Rotary Total Depth

CASING RECORD

Set 8-5/8" surface casing at 325'
cemented with 275 sacks

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

MAY 18 1950

STATE OF KANSAS

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #4 Smith located SE NW SW 24-22-14, Stafford Co., Kansas.

ANSCHUTZ DRILLING COMPANY

By: H. R. Jensen

Subscribed and sworn to before me this 16th day of May, 1950.

Martha Doye
Notary Public

My commission expires September 12, 1953

PLUGGING
FILE SEC. 24-22-14
BOOK PAGE 5 LINE 10