


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 24 Twp. 22 Rge. 14 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW - SW - NW
Lease Owner Spector Pipe and Supply Inc.
Lease Name Eggebecht Well No. 1
Office Address Box 169, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 2-19-50 19____
Application for plugging filed 4-3-66 19____
Application for plugging approved 4-4-66 19____
Plugging commenced April 18, 1966 19____
Plugging completed April 22, 1966 19____
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Anchie V. Elving Pratt, Kansas
Producing formation Arbuckle Depth to top 3794' Bottom 3795' Total Depth of Well 3796' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	414'	none
				5 1/2"	3795'	2679.43'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3775 feet and dumped 5 sacks of cement. Built 10 foot Rock Bridge at 300 feet and dumped 25 sacks of cement. Mudded hole to 40 feet and dumped 10 sacks.

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 - 1966

5-2-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing and Pulling Co.
Address R. Rt 4, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Spector Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of April, 1966

My commission expires March 9, 1970
W. H. Dawson Notary Public.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Eggebrecht No. 1

SEC. 24 T. 22 R. 14W
SW SW NW
330' N, 330' E of W/4 cor.

Total Depth. 3796 SLM
3781 P.B.
Comm. 1-9-50 Comp. 2-19-50
Shot or Treated. Acidized 3000 gals
Contractor. Hdr.-Louis Drilling Co.
Issued. 4-29-50

County. Stafford
KANSAS



Elevation.

Production. Phy pot. 296 oil,
69 wtr

Figures Indicate Bottom of Formations.

sand, gravel	103
sand	170
sand, shale, shells	325
shale, shells	340
red bed, shale	380
red bed	417
sand, shale, red bed	810
shale	1100
shale, shells	1645
lime, shale	1700
shale, lime shells	1790
lime	1890
lime, shale	2025
shale	2070
lime, shale	2395
shale	2460
lime, shale	2710
shale	2830
shale, lime	2910
lime	2935
lime, shale	3140
lime	3180
shale	3230
lime	3375
lime, shale	3450
lime	3490
lime, shale	3521
lime	3715
shale, lime	3793
lime	3798

3798 RTD = 3796 SLM

Total Depth P.B. 3781

Tops:

Corr. Lansing	3447
" Viola	3713
" Simpson	3743
" Arbuckle	3794

Drilled cement to 3781 SLM.

Perf. 36 shots 3508-20 50 gals.
fluid (90% oil) in 1 3/4 hrs.

2-25-50 Acidized 2000 gals. 3508-20.

2-27-50 Pumped 139 oil, 139 wtr,
24 hrs.

Set retainer at 3470 and squeezed
with 112 sacks cement; 90 sacks
through perforations at 3100.

Drilled cement to 3781 SLM.

Perf. 37 shots 3507-14.

3-3-50 Acidized 1000 gals. 3507-14

3-5-50 Pumped 235 oil, 66 wtr, 24 hrs

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1966
CONSERVATION DIVISION
Topeka, Kansas