


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Stafford County. Sec. 27 Twp. 22S Rge. 14 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SW NE

Lease Owner Petroleum, Inc.

Lease Name Garvin "G" Well No. 2

Office Address 300 W. Douglas, Wichita, KS 67202

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry hole

Date Well completed 4-18 1980

Application for plugging filed 4-18-1980

Application for plugging approved 4-18 1980

Plugging commenced 4-18 1980

Plugging completed 4-18 1980

Reason for abandonment of well or producing formation

Dry hole

If a producing well is abandoned, date of last production

19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well William T. Owen

Producing formation Depth to top Bottom Total Depth of Well 3940'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	260'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

40 sacks @ 540'

40 sacks @ 270'

10 sacks @ 40'

10 sacks in rathole

50/50 pozmix 4% Gel

By Sun Cementing

4-18-80

RECEIVED
MAY 12 1980
KANSAS CORPORATION COMMISSION
WICHITA, KANSAS

(If additional description is necessary use BACK of this sheet)

Name of Plugging Contractor

ALLEN DRILLING CO.

P. O. BOX 1389

GREAT BEND, KANSAS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Dale Smith

(employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Dale L. Smith

Box 1389, Great Bend, KS 67530


(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1980

Wanda Nichols

Notary Public.

My commission expires 12-10-83



DRILLER'S WELL LOG

DATE COMMENCED: 4-7-80
DATE COMPLETED: 4-18-80

Petroleum, Inc.
Garvin "G" #2
SE SW NE, Sec. 27-22s-14w
Stafford County, KS

ELEVATIONS K.B. 1942'
G.L. 1937'

FORMATION DATA

3349-3354' Shale
3354-3380' Shale
3380-3478' Shale
3478-3492' Lime & Shale
3492-3723' Lime
3723-3814' Lime & Shale
3814-3853' Chert
3853-3906' Sand
3906-3940' Dolomite
3940' RTD

Anhydrite
Heebner 3349'
Douglas 3380'
Brown Lime 3478'
Lansing 3492'
Base Kansas City 3723'
Viola 3814'
Simpson 3853'
Arbuckle 3906'
RTD 3940'

SURFACE PIPE:

Ran new 8 5/8" 20# casing.
225 sks. 60/40 Pozmix
2% Gel., 3% c.c.

PLUGGING:

40 sacks @ 540'
40 sacks @ 270'
10 sacks @ 40'
10 sacks in rathole
50/50 Pozmix, 4% Gel
by Sun Cementing
4-18-80


AFFIDAVIT

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Dale Smith, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Dale L. Smith

Subscribed and sworn to before me this 2nd day of May, 1980.



Wanda Nichols
(Notary Public)

My commission Expires: 12-10-83