


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County, Sec. 27 Twp. 22 Rge. (E) 14 (W)  
Location as "NE/CNW&SWW" or footage from lines SWC SW NE/4  
Lease Owner Woody Speer  
Lease Name Morris Garvin Well No. B-1  
Office Address 708 Petroleum Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry  
Date well completed 11/17 19 52  
Application for plugging filed 11/17 19 52  
Application for plugging approved 11/17 19 52  
Plugging commenced 11/17 19 52  
Plugging completed 11/17 19 52  
Reason for abandonment of well or producing formation dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durker  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3945 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	324	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy Rotary mud, set plug  
at 250 ft. ran 20 sacks cement through drill  
pipe. Filled with mud, set plug and 5 sacks  
cement at the surface.

11-21-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor M. B. Armer  
Address 710 Petroleum Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick  
L. C. Sponenberg (employee of owner, or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg


(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of November, 1952

Lorraine M Johnson

Notary Public.

My commission expires Oct. 13, 1956.



L O G

Company: Woody Speer  
 Contractor: M. B. Armer (Ideco Rig)  
 Drilling Commenced: 11/5/52  
 Drilling Completed: 11/17/52  
 Elevation: 1938 Gr.  
 1940 D.F.

Farm: Garvin No. 1  
 Location: SWc SW NE Sec. 27-22S-11W  
 Stafford County, Kansas  
 Casing Record: 8-5/8" casing at 324'  
 with 200 sacks Pozmix.

(figures below indicate bottoms)

Surface Clay & Sand	210
Shale	225
Shale & Shells	324
Sand	595
Red Bed	856
Red Bed, Shale & Shells	1335
Shale & Shells	1692
Shale & Lime	2430
Shale & Shells	2930
Broken Lime	3065
Lime & Shale	3165
Broken Lime	3250
Shale & Lime	3522
Lime	3734
Shale	3817
Shale & Lime	3855
Shale	3914
Lime	3945
R.T.D.	3945

FORMATION TOPS (R.B. MEAS.)

Heebner	3357
Brown Lime	3483
Lansing	3493
Viola	3806
Simpson	3857
Arbuckle	3914

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

RECEIVED  
 STATE CONSERVATION COMMISSION

NOV 21 1952

CONSERVATION DIVISION  
 Wichita, Kansas

By: *P. L. Sprenberg*

STATE OF KANSAS

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 20th day of November, 1952.

*Hazel Walters*  
 Notary Public

My Commission Expires: Sept. 17, 1955.

