

*HE*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 3 1963

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

10-3-63

Operator's Full Name E. K. Edmiston

Complete Address: 501 1st National Bank Bldg., Wichita, Kansas

Lease Name Alpers Well No. # 1

Location NE NW NE Sec. 21 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3870

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A      X     

Other well as hereafter indicated:     

Plugging Contractor: E. K. Edmiston

Address: 501 1st National Bank Bldg., Wichita, Kans. License No.     

Operation Completed: Hour 9:00PM Day 30th Month Sept. Year 1963

The Above well was plugged as follows:

244' of 8 5/8" surface pipe, cemented with 200 sacks. Fluid level was  
up in the hole. 1st cementing plug and 1/2 sack hulls was pushed to 240',  
cemented with 25 sacks through the drill pipe. Hole was filled with  
drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack hulls,  
cemented with 10 sacks to base cellar. Rat hole bridged and cemented  
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

10/3/63  
4835-W

Signed: Archie Elving  
Well Plugging Supervisor