

15-185-19360-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1965

1-21-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alpine Oil & Royalty Co., Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name Eleanor Rusco Well No. # 1

Location SW NE SW Sec. 21 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3837'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 3:30PM Day 19th Month Jan. Year 1965

The Above well was plugged as follows:

323' of 8 5/8" surface pipe, cemented with 275 sacks. 3834' of 5 1/2" long
string, cemented with 150 sacks. Bottom of the hole was sanded to 3825',
and cemented with 5 sacks. 2804' of 5 1/2" long string was recovered from
the hole. Fluid was up in the hole. Bridge plug was pushed to 300', and
10' of rock bridge on plug. 2 sacks of cement was mixed in barrel with
5% Calcium Chloride and put on plug at 290', through dump bailer, and
let set 2 hours, hole was bailed down, and 23 sacks of cement was added
to plug. Hole was filled with mud to 40', and 10' of rock bridge, and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/21/65

INV. NO. 569-W

Signed: Archie Elving
Well Plugging Supervisor