

Form CP-3  
Rev. 6-26-62

*MP*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 8 1963  
10 8 63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name L. K. Parrish

Complete Address: 714 National Bank Bldg., Wichita, Kansas

Lease Name Hahn Well No. # 1

Location NE NE NW Sec. 22 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3821

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: C-G Drilling Co.

Address: 107 Rule Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 7:00PM Day Oct. Month 2nd Year 1963

The Above well was plugged as follows:

312' of 8 5/8" surface pipe, cemented with 300 sacks. Fluid level in  
hole was at 297'. 1st cementing plug was set on fluid at 297', bridged  
with 1/2 sack hulls, cemented with 25 sacks. Hole was filled with drilling  
mud to 40', 2nd cementing plug, bridged with 1/2 sack hulls, cemented with  
10 sacks to base cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 10/9/63  
INV. NO. 9849-4

Signed: Audie Elving  
Well Plugging Supervisor