

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSIONJ. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, KansasFEB 27 1964  
2-27-64  
CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Inger Oil Co.Complete Address: 1020 Central Bldg., Wichita, KansasLease Name Inger Well No. # 1Location SE SW SW Sec. 22 Twp. 22 Rge. 13 (E) (W) WCounty Stafford Total Depth 3830Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling Co.Address: Box 304, Chase, Kansas License No. 436Operation Completed: Hour 12:30PM Day 26th Month Feb. Year 1964

The Above well was plugged as follows:

332' of 8 5/8" surface pipe, cement circulated. 3827' of 5 1/2" long string,  
cemented with 100 sacks. Bottom of hole was sanded to 3810', and cement-  
ed with 5 sacks. Hole was bailed down to 225'. Plug was set at 225', with  
10' rock bridge, and cemented with 25 sacks. Hole was filled with mud to  
40', with 10' rock bridge, and cemented with 10 sacks to base cellar.  
2840' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving

Well Plugging Supervisor

DATE 2/28/64INV. NO. 8915-W