

KANSAS

W
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1966

4-25-66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address: P. O. Box 169, Russell, Kansas

Lease Name Eggebrecht Well No. # 1

Location SW SW NW Sec. 24 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3796'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Company

Address: Route 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 10:30AM Day 22nd Month April Year 1966

The Above well was plugged as follows:

414' of 8 5/8" surface pipe, cemented with 300 sacks. 3781' of 5 1/2" long
string, cemented with 200 sacks. This is an open hole. Bottom of the hole
was sanded to 3775', and cemented with 5 sacks, through the dump bailer.
Bridge plug was pushed in fluid to 300', rock bridge from 300' to 290'.
8 sacks of cement was mixed in a barrel and put on plug at 290', through
the dump bailer, and let set over-night. Next day hole was bailed dry, and
17 sacks of cement was added to the plug. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar. 2672' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 4/26/66
INV. NO. 3099-W