

Form CP-3  
Rev. 6-26-62

KANSAS

10  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1966  
CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Specter Pipe & Supply, Inc. 4-28-66Complete Address: P. O. Box 169, Russell, KansasLease Name Eggebrecht Well No. # 3Location NW SW NW Sec. 24 Twp. 22 Rge. 14 (E) (W) WCounty Stafford Total Depth 3798'Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A Other well as hereafter indicated: Plugging Contractor: Lynch Casing Pulling CompanyAddress: Route 4, Great Bend, Kansas License No. 457Operation Completed: Hour 10:15 AM Day 27th Month April Year 1966

The Above well was plugged as follows:

415' of 8 5/8" surface pipe, cemented with 300 sacks. 3790' of 5 1/2" long string, cemented with 150 sacks. This is an open hole. Bottom of the hole was sanded to 3775', and cemented with 5 sacks, through the dump bailer.2918' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 300', rock bridge from 300' to 290'. 8 sacks of cement was mixed in a barrel, and put on plug at 290', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 17 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

4/28/66

INV. NO.

3122-W

Signed:

Archie Elving  
Well Plugging Supervisor