

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JAN 2 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued December 13, 1967.

*Rec'd
12-1-67*

Operator's Full Name Aspen Drilling Company

Complete Address: P. O. Box 783, Great Bend, Kansas 67530

Lease Name Gates Well No. # 1

Location NE NW NE Sec. 34 Twp. 22 Rge. 11 (E) (W) W

County Stafford Total Depth 3623'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 9:30AM Day 30th Month December Year 1967

The Above well was plugged as follows:

204' of 8 5/8" surface pipe, cemented with 240 sacks. 3619' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded to
3600', and cemented with 5 sacks, through the dump bailer, with cement from 3600'
to 3560'. 2980' of 5 1/2" long string was recovered from the hole. Bridge plug was
pushed in fluid to 200', bridge plug and rock bridge from 200' to 190'. 6 sacks of
cement was mixed in a barrel, and put on plug at 190', through the dump bailer, and
let set over-night. Next day hole was bailed dry, and 19 sacks of cement was added
to the plug, with cement from 190' to 115'. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Achie Elving*
Well Plugging Supervisor

DATE 1-2-68
INV. NO. 7016-W