

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Gabbert-Jones, Inc. 15-185-30247-0000

Complete Address: 514 Orpheum Bldg., Wichita, Kansas

Lease Name Brock Well No. # 1

Location SW NW SW Sec. 8 Twp. 23 Rge. 11 (E) (W) W

County Stafford Total Depth 3730'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones, Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 12:00PM Day 14th Month May Year 1966

The Above well was plugged as follows:

282' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid
level in the hole was at 260', 1st cementing plug bridged with 1/2 Sack
of hulls on fluid at 260', and cemented with 25 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of
hulls on fluid at 40', and cemented with 10 sacks to the base of the
cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/17/66
INV. NO. 3236-U

Signed: Audie Elving
Well Plugging Supervisor