

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply Inc.

15-185-01415-0000

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Howe Well No. # 1

Location SE SE NW Sec. 26 Twp. 23 Rge. 11 (E) (W) W

County Stafford Total Depth 3740'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe & Supply Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 10:30AM Day 21st Month April Year 1965

The Above well was plugged as follows:

241' of 8 5/8" surface pipe, cemented with 210 sacks. 3739' of 4 1/2" long
string, cemented with 100 sacks. Plug back to 3705'. Top perforation 3666'.

Bottom of the hole was sanded to 3650', and cemented with 3 sacks. 3185'
of 4 1/2" long string was recovered from the hole. Fluid was up in the hole.

Bridge plug was pushed in fluid to 235', and 10' of rock bridge on plug.

7 sacks of cement was mixed in barrel, and put on plug at 225', through

the dump bailer. And let set over-night. Next morning hole was bailed dry,
and 18 sacks of cement was added to the plug. Hole was filled with mud to
40', and 10' of rock bridge, and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/22/65

INV. NO. 1031-W