

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR F & M OIL CO., INC.

API NO. 15-145-20,916-0000

ADDRESS 422 Union Center

COUNTY Pawnee

Wichita, Kansas 67202

FIELD _____

**CONTACT PERSON Preston Burkey

PROD. FORMATION _____

PHONE 913-483-5295

LEASE Branstetter "D"

PURCHASER _____

WELL NO. 1

ADDRESS _____

WELL LOCATION NW NE NE

DRILLING Union Drilling Co., Inc.

330 Ft. from North Line and

CONTRACTOR _____

990 Ft. from East Line of

ADDRESS 422 Union Center

the SEC. 36 TWP. 22S RGE. 15W

Wichita, Kansas 67202

PLUGGING Sun Oil Well Cementing, Inc.

CONTRACTOR _____


ADDRESS Box 169

Great Bend, Kansas 67530

TOTAL DEPTH 4080' PBTD _____

SPUD DATE 11-18-81 DATE COMPLETED 11-26-81

ELEV: GR 1973 DF _____ KB 1982



WELL PLAT

KCC _____
KGS _____
MISC
(Office Use)

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS (New) / (Used) casing.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"		527'	posmix common	150 150	60/40 2% gel, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

12-3-81

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

RECEIVED
STATE CORPORATION COMMISSION
Depth Interval treated

DEC - 3 1981

CONSERVATION DIVISION
Wichita, Kansas

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____ Gravity _____

RATE OF PRODUCTION PER 24 HOURS
Oil _____ bbls. Gas _____ MCF Water _____ % Gas-oil ratio _____ bbls.

Disposition of gas (vented, used on lease or sold) _____ Perforations _____

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Unkown Depth Unkown

Estimated height of cement behind Surface Pipe to surface.

DV USED? None

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
DST# 1 3676-3700', 30-45-60-45, wk to fr blow, rec 70' VSOCM, 120' VSOCMW, 240' OSW, IFP 81-110#, ISIP 1375#, FFP 140-177#, FSIP 1353#, BHT 104'.			<u>Sample Tops:</u>	
			Tarkio	2830 (- 848)
DST#2 3706-40', 30-45-60-45, wk to fr blow, rec 140' WM w/show of oil in tool, IFP 88-81#, ISIP 838#, FFP 103-103#, FSIP 794#, BHT 103'.			Elmont	2895 (- 913)
			Howard	2970 (- 988)
			Topeka	3043 (-1061)
			Heebner	3423 (-1441)
			Toronto	3405 (-1463)
			Douglas	3461 (-1479)
			Br/Lime	3549 (-1567)
			Lansing	3558 (-1576)
			RTD	4080 (-2098)
			<u>Electric Log Tops:</u>	
			Anhydrite	906 (+1076)
			Tarkio	2828 (- 846)
			Elmont	2892 (- 910)
			Howard	2964 (- 982)
			Topeka	3040 (-1058)
			Heebner	3422 (-1440)
			Toronto	3444 (-1462)
		Doug Sh	3461 (-1479)	
		Br/Lime	3548 (-1566)	
		Lansing	3557 (-1575)	
		B/KC	3790 (-1808)	
		Cgl Sh	3875 (-1893)	
		Viola	3924 (-1942)	
		Simpson Sh	3994 (-2012)	
		Arbuckle	4051 (-2069)	
		LTD	4079 (-2097)	

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS,

Robert B. Jinkins OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS VP Exploration (FOR)(OF) F & M OIL CO., INC.

OPERATOR OF THE Branstetter "D" LEASE, AND IS DULY AUTHORIZED TO MAKE,

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 26th DAY OF November, 19 81, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(s) Robert B. Jinkins

SUBSCRIBED AND SWORN BEFORE ME THIS 1st DAY OF December 19 81

Shirley A. Gallegos
NOTARY PUBLIC
Shirley A. Gallegos

