

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR F & M OIL CO., INC.

API NO. 15-145-20,916-0000

ADDRESS 422 Union Center
Wichita, Kansas 67202

COUNTY Pawnee

FIELD W. C.

**CONTACT PERSON Preston Burkey
PHONE 913-483-5295

PROD. FORMATION _____

LEASE Branstetter "D"

PURCHASER _____
ADDRESS _____


WELL NO. 1

WELL LOCATION NW NE NE

DRILLING CONTRACTOR Union Drilling Co., Inc.
ADDRESS 422 Union Center
Wichita, Kansas 67202

330 Ft. from North Line and
990 Ft. from East Line of
the SEC. 36 TWP. 22S RGE. 15W

PLUGGING CONTRACTOR Sun Oil Well Cementing, Inc.
ADDRESS Box 169
Great Bend, Kansas 67530



TOTAL DEPTH 4080' PBTD _____

SPUD DATE 11-18-81 DATE COMPLETED 11-26-81

ELEV: GR 1973 DF _____ KB 1982

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS (New) / (Used) casing.
CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8-5/8"		527'	posmix common	150 150	60/40 2% gel, 3% CC

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
	RECEIVED STATE CORPORATION COMMISSION
	DEC - 3 1981

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity	CONSERVATION DIVISION Wichita, Kansas
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water %
Disposition of gas (vented, used on lease or sold)		Gas-oil ratio	Perforations

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Unkown Depth Unkown

Estimated height of cement behind Surface Pipe to surface.

DV USED? None

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
DST# 1 3676-3700', 30-45-60-45, wk to fr blow, rec 70' VSOCM, 120' VSOCMW, 240' OSW, IFP 81-110#, ISIP 1375#, FFP 140-177#, FSIP 1353#, BHT 104'.			Sample Tops:	
			Tarkio	2830 (- 848)
DST#2 3706-40', 30-45-60-45, wk to fr blow, rec 140' WM w/show of oil in tool, IFP 88-81#, ISIP 838#, FFP 103-103#, FSIP 794#, BHT 103'.			Elmont	2895 (- 913)
			Howard	2970 (- 988)
			Topeka	3043 (-1061)
			Heebner	3423 (-1441)
			Toronto	3405 (-1463)
			Douglas	3461 (-1479)
			Br/Lime	3549 (-1567)
			Lansing	3558 (-1576)
			RTD	4080 (-2098)
			Electric Log Tops:	
			Anhydrite	906 (+1076)
			Tarkio	2828 (- 846)
			Elmont	2892 (- 910)
			Howard	2964 (- 982)
			Topeka	3040 (-1058)
			Heebner	3422 (-1440)
			Toronto	3444 (-1462)
Doug Sh	3461 (-1479)			
Br/Lime	3548 (-1566)			
Lansing	3557 (-1575)			
B/KC	3790 (-1808)			
Cgl Sh	3875 (-1893)			
Viola	3924 (-1942)			
Simpson Sh	3994 (-2012)			
Arbuckle	4051 (-2069)			
LTD	4079 (-2097)			

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS,

Robert B. Jenkins OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS VP Exploration (FOR)(OF) F & M OIL CO., INC.

OPERATOR OF THE Branstetter "D" LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 26th DAY OF November, 1981, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Robert B. Jenkins

SUBSCRIBED AND SWORN BEFORE ME THIS 1st DAY OF December 1981



Shirley A. Gallegos
NOTARY PUBLIC
Shirley A. Gallegos