

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

15-055-10160-0001

WELL PLUGGING APPLICATION FORM  
(File One Copy)

6/8/88

API NUMBER Pre 1967 (of this well) Drilled in Aug. 1948  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petroleum Production Management, Inc. OPERATORS LICENSE NO. 6234

ADDRESS 200 Sutton Place Bldg., Wichita, KS. 67202 PHONE # (316) 265-4651

LEASE (FARM) Nunn Pool Unit  
Nunn WELL NO. 5W WELL LOCATION SE NE-~~SW~~ 1/4 COUNTY Finney

SEC. 27 TWP. 21 RGE. 34 (X) or (W) TOTAL DEPTH 4720' PLUG BACK TD 4468'

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. 70,043C  
C-9779

SURFACE CASING SIZE 8-5/8 SET AT 270' CEMENTED WITH 175 SACKS

CASING SIZE 5 1/2" SET AT 4490' CEMENTED WITH 225 SACKS

PERFORATED AT 4299-4311' (Marmaton)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Casing collapsed or parted @ 1320' - cannot

get past this depth w/tubing. Recommend running tubing to ± 1320', pump 5 sx. Gel followed

by 125 sx. 60/40 Pozmix w/6% Gel & pull tbg. Fill csg. to surface. Tie into 5 1/2" - 8-5/8" ann.  
& pump 100 sx. 60/40 (If additional space is needed use back of form)  
Poz., 6% Gel. Above as per recommendation of Steve Durrant.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10 a.m. June 22, 1988

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ernest Boque PHONE # (316) 278-6928 Res. 278-7410

ADDRESS RR #2 - Holcomb, KS. 67851

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. JUN - 2 1988

ADDRESS Liberal, Kansas PHONE # (316) 624-3879 CONSERVATION DIVISION  
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Steve Park  
(Operator or Agent)

DATE: May 31, 1988

①

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

June 3, 1988

SEP 3 '88

WELL PLUGGING NOTICE

EXPIRES

Nunn Pool Unit #5W (Inj.)  
SE NE SW  
Sec. 27-21S-24W  
Finney County

Petroleum Production Management, Inc.  
200 Sutton Place Bldg.  
Wichita, KS 67202


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

  
\_\_\_\_\_  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760