

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

15-055-10159-0001
RECEIVED
STATE CORPORATION COMMISSION
JUL - 7 1989
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 3-8-48 (of this well) 6/90
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petroleum Production Management, Inc. OPERATORS LICENSE NO. 6234

ADDRESS 200 Sutton Place Bldg., Wichita, KS. 67202 PHONE # (316) 265-4651

LEASE (FARM) Nunn WELL NO. 4 WELL LOCATION NW/4 NE/4 COUNTY Finney

SEC. 27 TWP. 21 RGE. 34 (X) or (W) TOTAL DEPTH 4725' PLUG BACK TD 4649'

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. E-9779

SURFACE CASING SIZE 10-3/4" SET AT 286' CEMENTED WITH 200 SACKS

CASING SIZE 5 1/2" SET AT 4661' CEMENTED WITH 300 SACKS

PERFORATED AT 4620-4640' (Miss) 4286-4295' (Marm)

CONDITION OF WELL: GOOD _____ POOR X CASING LEAK _____ JUNK IN HOLE 2-7/8" tbg.

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Wash over 2-7/8" tbg. to below Dakota (\pm 800'). Run 1" down 5 1/2"-10-3/4" annulus to 330'. Circ. clean. Pump 400 sx. dn. tbg. to fill 5 1/2" to surface. Pull tbg. Pump 125 sx. dn. 1" to fill annulus 44' below 10-3/4" to surface. Pull 1" - cut off 5 1/2" & 10-3/4" 4' below ground level & weld plate.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN July 24, 1989 9:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Steve Park PHONE # (316) 265-4651

ADDRESS 200 Sutton Place Bldg., Wichita, KS. 67202

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. _____

ADDRESS P. O. Box 1598, Liberal, KS. 67901 PHONE # (316) 624-3879

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Steve Park
(Operator or Agent)

DATE: July 6, 1989

(1)



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
OCT 10 1989
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

July 10, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Petroleum Production Management, Inc.
200 Sutton Place Bldg.
Wichita, KS 67202

Nunn #4 (Inj.)
NW/4 NE/4
Sec. 27-21S-34W
Finney County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760