

Me
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1965
1-18-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Great Bend Pipe & Supply
Complete Address: Drawer B Great Bend, Kans
Lease Name Sutton Well No. 1
Location NE NE NW Sec. 27 Twp. 22 Rge. (E) (W) 15
County Pawnee Total Depth 3992
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kans License No. 436
Operation Completed: Hour 6PM Day 14 Month 1 Year 65

The Above well was plugged as follows:

8 5/8" 224' circulated with cement - 5 1/2" 3989' with 75 sax cement
Perf at 5976'
Sand back to 3965', set 4 sax cement with dump bailer, pulled 3474'
5 1/2" to 550', circulated hole with heavy mud (20 sax Gel), pulled
5 1/2" to 350', displaced 20 sax cement through 5 1/2" at 350', heavy mud
to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to
35', cement 35' to ~~0~~ 0'

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edson Petty
Well Plugging Supervisor

DATE 1/18/65
INV NO. 503-14