

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

R
15-185-12819-0001

FILE NO. 9-4
LOCATION SE-7E-1W
SEC. 28 TWP. 23 RGE. 12W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Gerdes

Operator McAdams Drilling Co. Address Bristow, Okla.

Field _____ County Stafford

Total Depth 3893 Feet.

Plugging Contractor Forbes Casing Pulling Co.

Plugging Contractor's License No. 49

Address Great Bend, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe 10 3/4" @ 227' cwc 5 1/2" casing set
3893' w/ 200 sv cem. P.B. 3849' top perf 3477'
Sanded hole to 3460' dumped 5 sv cem.
Shot off and pulled 5 1/2" casing. Filled
hole with heavy mud to 225' set rock
bridge and dumped 20 sv cem. mud to
25' rock bridge and 10 sv cem. to base

RECEIVED
STATE CORPORATION COMMISSION
NOV - 1 1955
CONSERVATION DIVISION
Wichita, Kansas

11-1-55

Warren H. Garner
District Conservation Agent

Date Oct 30, 1955

PLUGGING
WELL SEC. 28 T23 R 12W
BOOK PAGE 9 LINE 4