

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-185-12333-0000

FILE NO. *NW 341 NW*

LOCATION *Sec. 24 1/4*

SEC. *28* TWP. *23* RGE. *12-W*

Dry Hole *X* Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. *1* Lease *Hayes*

Operator *Benson Drilling Co. Inc.* Address *333 First N. Bk. Bldg. Wichita-Kans.*

Field _____ County *Stafford*

Total Depth *3858* Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2" - 158 ft. Circulated with cement
5 1/2" casing set at 3849 ft. Cemented with 100 sacks cement
Plugged back to 3840 ft. with shot - dumped 5 sacks
of cement at 3840 ft. Shot off & pulled the 5 1/2" casing
Filled with mud to 158 ft. Set Rock Bridge
& 15 sacks of cement at 158 ft. Mud to 30 ft.
Plug & 10 sacks of cement at the surface.*

RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1950

C. D. Stough
District Conservation Agent

Date *12-12-50*

PLUGGING
FILE SEC. *28* TWP. *23* R. *12W*
BOOK PAGE *49* LINE *17*

[Handwritten signature]