

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name Krey Well No. # 1

Location NE NE NW Sec. 3 Twp. 22 Rge. 14 (E) W

County Stafford Total Depth 3787'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:45 PM Day 4th Month Nov. Year 1965

The Above well was plugged as follows:

245' of 8 5/8" surface pipe, cement circulated. 3780' of 4 1/2" long string,
cemented with 175 sacks. Top perforation 3450'. Plug was pushed to 3450',
and 50' of sand, and cemented with 3 sacks. 1996' of 4 1/2" long string was
recovered from the hole. Fluid was up in the hole. Bridge plug was pushed
in fluid to 240', rock bridge from 240' to 230'. 2 sacks of Cal-Seal was
mixed in barrel, and put on plug through dump bailer at 230', and let set
for 2 hours. Hole was bailed dry, and 25 sacks of cement was added to the
plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cements
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/9/65

INV. NO. 2151-111