

15-185-13163-00-01

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc., c/o Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Curtis (Smallwood Kan-Kc Unit # 1-1) Well No. C-1

Location SE SE NE Sec. 3 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3825'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 10:45 AM Day 8th Month March Year 1966

The Above well was plugged as follows:

220' of 8 5/8" surface pipe, cemented with 175 sacks. 3685' of 4 1/2" long
string, cemented with 50 sacks. Plug back TD 3650'. Top perferation 3565'.
Bottom of the hole was sanded to 3550', and cemented with 3 sacks, through
dump bailer. 3189' of 4 1/2" long string was recovered from the hole. Fluid was
up in the hole. Bridge plug was pushed in fluid to 220', rock bridge from 220'
to 210'. 8 sacks of cement was mixed in barrel, and put on plug at 210',
through the dump bailer, and let set over-night. Next morning hole was baile
dry, and 17 sacks of cement was added to the plug. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base
of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Achie Elving
Well Plugging Supervisor

DATE 3/14/66
INV. NO. 2851-W