

Form CP-3  
Rev. 6-26-62

M  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

MAR 18 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc., c/o Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Curtis (Smallwood Lan-KC unit #1-2) Well No. # C-2

Location NE SE NE Sec. 3 Twp. 22 Rge. 14 (E) (W)W

County Stafford Total Depth 3840'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Puller, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 12:30PM Day 14th Month March Year 1966

The Above well was plugged as follows:

230' of 8 5/8" surface pipe, cemented with 200 sacks. 3732' of 4 1/2" long  
string, cemented with 100 sacks. Plug back T.D. 3667'. Top perferation 3579'  
Bottom of the hole was sanded to 3570', and cemented with 3 sacks, through  
the dump bailer. 2765' of 4 1/2" long string was recovered from the hole. Bridg  
plug was pushed in fluid to 230', rock bridge from 230' to 220'. 10 sacks of  
cement was mixed in a barrel, and put on plug at 220', through the dump bail  
er, and let set over-night. Next day hole was bailed dry, and 15 sacks of  
cement was added to the plug. Hole was filled with mud to 40', rock bridge  
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 3/18/66

INV. NO. 2891-W