

Form CP-3
Rev. 6-26-62K
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

AUG 19 1964

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Mountain Iron & SupplyComplete Address: Second & Broadway, Wichita, KansasLease Name McBride Well No. # 1Location NW SE NE Sec. 14 Twp. 22 Rge. 14 (E) (W)WCounty Stafford Total Depth 3850Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Knight Casing Pulling CompanyAddress: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 11:30AM Day 18th Month August Year 1964

The Above well was plugged as follows:

299' of 8 5/8" surface pipe, cement circulated. 3840' of 4 1/2" long string,
cemented with 100 sacks. Top of cement 3350'. Bottom of the hole was sand-
ed to 3830', and cemented with 3 sacks. Fluid level was up in the hole.
Bridge plug was set at 275', and 10' of rock bridge. 5 sacks of cement
was mixed in barrel and put on plug, at 265', through dump bailer, and
let set over-night. Next morning hole bailed down, and 20 sacks of cement
was added to the plug. Hole was filled with mud to 40', and 10' of rock
bridge, cemented with 10 sacks to the base of the cellar.

3300' of 4 1/2" long string was recovered from the hole.
I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

8/19/64

Signed:

Archie Elving
Well Plugging Supervisor