

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

APR 02 1976  
4-2-76

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

Geological Survey  
Wichita, Kansas

API Number 15-145-20374-0000 (of this well)

Operator's Full Name F & M Oil Company

Complete Address 505 Union Center, Wichita, Kansas 67202

Lease Name Murphy Well No. 1

Location SE NW SW Sec. 36 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 4065'

Abandoned Oil Well        Gas Well XX Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 12<sup>N</sup> Day 1 Month 4 Year 1976

The above well was plugged as follows:

Total Depth 4065' 8 5/8 csg set 241' cwc 225 sk.

4 1/2 csg set 4052' cw 150 sk cem.

4 1/2 csg PFS (3923') W/PBTD 4030'

Filled 4 1/2 csg W/sd (4030'-3900') dumped 4 sk cmt W/dump bailer. (3900'-3865')

Cutoff & recovered 3000' of 4 1/2 csg.

Mixed & pumped down 8 5/8 csg With 25 sk gel & water -100 lbs hulls -released plug

& 100 sk comm cem 2% gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo Murrey  
Well Plugging Supervisor

INVOICED

DATE 4-05-76

INV. NO. 2997-W