

15-185-00746-0001

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202Well Plugging Authority,
issued November 6, 1967.RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1967

CONSERVATION DIVISION
Wichita, Kansas

11-27-67

Operator's Full Name Monarch Oil & Gas CompanyComplete Address: 1005 Wichita Plaza Bldg., Wichita, Kansas 67202Lease Name Dralle Well No. # A-2Location NE NE NE Sec. 16 Twp. 22 Rge. 14 (E) (W) WCounty Stafford Total Depth 3934'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Forbes Casing Pulling, Inc.Address: Box 221, Great Bend, Kansas 67530 License No. 49Operation Completed: Hour 11:00AM Day 20th Month November Year 1967

The Above well was plugged as follows:

306' of 8 5/8" surface pipe, cemented with 150 sacks. 3905' of 5 1/2" long string,
cemented with 150 sacks. Plug back T.D. 3650'. Top perforation 3589'. Bottom of
the hole was sanded to 3550', and cemented with 5 sacks, through the dump bailer.
1820' of 5 1/2" long string was recovered from the hole. Hole was squeezed. 10 sacks
of Gel-Mud and 75 sacks of cement was pumped in to the surface pipe to a pressure
of 200 lbs., pumped through an 8 5/8" swage, with cement from 225' to the base
of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging SupervisorDATE 11-28-67INV. NO. 6756-W