

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-185-12684-0000

FILE NO. 128-27

LOCATION C E/2-NW-SW

SEC. 36 TWP. 23 RGE. 11 W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 2 Lease O. Volker

Operator Republic Natural Gas Co. Address Box 126, Elliswood, Kans.

Field County Stephens

Total Depth 3744 Feet.

Plugging Contractor Morgan Well Plugging Serv.

Plugging Contractor's License No. 43

Address Hutchinson, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 10 3/4" @ 336' c.w.c. 7" O.D. set 3704'
w/ 100 sq Cem. Plugged back to 3699' top perf.
3692'. Filled back with Chat to 300'
dumped 5 sq Cem. Shot off and pulled 7"
Casing. Filled hole with heavy mud to
300' set rock bridge and dumped 25 sq Cem.
mud to 30' rock bridge and 15 sq Cem.
to base of cellar

7-1-55

RECEIVED
STATE CORPORATION COMMISSION

Warren H. Horner
District Conservation Agent

JUL 1 - 1955

Date June 27, 1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 36 T. 23 R. 11 W.
BLOCK PAGE 138 LINE 27