

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-185-12647-0000

FILE NO. 22-23

LOCATION E 1/2 - 22 E 1/4 - 8 W 1/2

SEC. 26 TWP. 23 RGE. 11-24

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease C. Walker

Operator Public Natural Gas Co. Address Box 126 Ellinwood - Kans.

Field \_\_\_\_\_ County Stephens

Total Depth 3751 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 13" - 283ft. Circulated with cement  
7 casing set at 3719ft. Plugged back to 2400ft with  
Mud-Lime Well Plug - Chart from 3454ft. to 3700ft. - Mixed  
5 sacks of cement at 2400ft. Ripped off & pulled the casing  
Filled with mud to 283ft. Set Rock Bridges & 20 sacks  
of cement at 283ft. Mud to 30ft. Bridges &  
10 sacks of cement at the surface -  
Bill Morgan - Plugging - Contractor -

9-6-50

1950

**PLUGGING**  
FILE SEC 36 T 23 R 11 W  
BOOK PAGE 22 LINE 23

C. H. Stough  
District Conservation Agent

Date 9-21-50