



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
*Recd*  
1-10-75

Operator's Full Name Fell & Wolfe Oil Co 15-185-11237-0000 CONSERVATION DIVISION  
Wichita, Kansas

Complete Address Box 7447 Tulsa, OK

Lease Name M Volker Well No. 1

Location C E/2 SE/SW Sec. 36 Twp. 23 Rge. 11 (E) (W)

County Stafford Total Depth 3730

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Art Lamb Casing Pulling

Address 2809 King Hutchinson, KS License No. 440

Operation Completed: Hour 3:00 PM Day 8 Month 1 Year 1975

The above well was plugged as follows:

280 ft 10 3/4 surface cement circulated. 3710 ft 7" long string  
cemented with 100 sacks. Top perf. 3705 ft. Sand to 3650 ft, 7  
sacks cement with bailer. Pulled 1748 ft 7" Pump 2 hulls, 10 gel,  
150 sacks cement to surface.

Pumped by Allied Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1/10/75

INV. NO. 029-W