

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 23-4 15485-11235-0000

LOCATION REP-157-SE SE, NW

SEC. 36 TWP. 23 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Sturgeon

Operator Republic Natural Gas Co Address Box 126 - Ellinwood - Kans.

Field _____ County Stafford

Total Depth 3701 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 13" - 228 ft - Circulated with cement.
7 casing set at 3724 ft. cemented - Plugged back to
3670 ft with Chert - Pumped 6 sacks of cement at 3670 ft
Ripped off & pulled the 7 casing - Filled with mud to
228 ft - Set Rock Bridge & 2 1/2 sacks of cement
at 228 ft - Mud to 3670 - Bridge & no sacks
of cement at the surface -
Bill Morgan - Plugging Contractor

SEP 13 1950 9-13-50

Signed C. M. Stough
District Conservation Agent

Date 9-11-50

PLUGGING
FILE SEC 36 TWP 23 RGE 11-W
BOOK PAGE 23 LINE 4