

*AP*

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 8 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply, Inc.

Complete Address Box 169, Russell, Kansas 67665

Lease Name Lingenfelder Well No. 1

Location C SW NW Sec. 16 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4493'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated None

Plugging Contractor Lynch Casing Pulling Co.

Address Great Bend, Kansas License No. 457

Operation Completed: Hour 4:00PM Day 6 Month 7 Year 1970

The above well was plugged as follows:

8 5/8" to 308' circulated w/ cement. 5 1/2" to 4475' cemented.

Open hole 4475' to 4493' Plug bottom w/ sand & 5 sacks cement.

Top of cement 3870' Mud 3870' to 850'

Spotted 80 sacks cement 850' to 550' Mud 550' to 300'

Spotted 30 sacks cement 300' to 200' Mud 200' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Company Pump

Pulled 362 1/2' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edward J. Eves*  
Well Plugging Supervisor

DATE 7/8/70  
INV. NO. 2184-W