

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

JAN 6 1965

CONSERVATION DIVISION
Wichita, Kansas

1-6-65

Operator's Full Name Rock Island Oil & Refining Co., Inc.Complete Address: 321 West Douglas, Wichita, KansasLease Name Miller "B" Well No. # 1Location C SW NE Sec. 16 Twp. 22 Rge. 22 (E) (W) WCounty Hodgeman Total Depth 4481'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling CompanyAddress: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 6:00PM Day 2nd Month Jan. Year 1965

The Above well was plugged as follows:

276' of 8 5/8" surface pipe, cement circulated. 4477' of 5 1/2" long string,
cemented with a temperature of 4151'. Bottom of the hole was sanded to
4470', and cemented with 5 sacks. Pipe was pulled up to 700', and 10 sacks
of Gel-Mud was pumped into 5 1/2". Pipe was pulled up to 600', and 25 sacks
cement was pumped into 5 1/2" swage. Pipe was pulled up to 275', and 25 sacks
of cement was pumped into 5 1/2" swage. Hole was bailed down to 55', and
bridge plug set on fluid at 55', and cemented with 15 sacks to the base
of the cellar. 3485' of 5 1/2" long string recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-6-65INV. NO. 482-WSigned: Aubie Clwing
Well Plugging Supervisor