

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name N. Appleman Company
 Complete Address: Box 1034, Garden City, Kansas 67846
 Lease Name Lingenfelder Well No. 2
 Location C SE NW Sec. 16 Twp. 22 Rge. 22 ~~23~~ (W)
 County Hodgeman Total Depth 4472'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated: None
 Plugging Contractor: Knight Casing Pulling Co.
 Address: Box 405, Chase, Kansas License No. 436
 Operation Completed: Hour 2:00PM Day 15 Month 5 Year 1968

The Above well was plugged as follows:

8 5/8" to 312' circulated w/ cement. 4 1/2" to 4465' cemented.
Open Hole to 4472' Plug bottom w/ sand & 5 sacks cement.
Top of cement 4370' Mud 4370' to 900'
Spotted 100 sacks cement 900' to 550' Mud 550' to 300'
Spotted 30 sacks cement 300' to 200' Mud 200' to 40'
Plug, Halls & 10 sacks cement 40' to 0&. Company Pump
Pulled 2788' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

5/17/68

INV. NO.

9761-W

Signed:

Edgar J. Egan
Well Plugging Supervisor