

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

5-2-72  
RECEIVED  
STATE CORPORATION COMMISSION  
MAY 2 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Drillers Production Co., Inc.  
Complete Address 480 4th Nat'l Bldg., Wichita, Kansas  
Lease Name Campbell "B" Well No. 1  
Location C W/2 NE SW Sec. 9 Twp. 22 Rge. 23 (E) (W)  
County Hodgeman Total Depth 4631'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated None  
Plugging Contractor Knight Casing Pulling  
Address Chase, Kansas License No. 624  
Operation Completed: Hour 11:00AM Day 25 Month 4 Year 1972

The above well was plugged as follows:

8 5/8" to 305' circulated w/ cement. 5 1/2" to 4619' cemented.  
12' of openhole 4619' to 4631' Plug bottom w/ sand & 5 sacks cement.  
Top of cement 4560' Mud 4560' to 850'  
Spotted 80 sacks cement 850' to 550' Mud 550' to 300'  
Spotted 30 sacks cement 300' to 200' Mud 200' to 40'  
Plug & 10 sacks cement 40' to 0'. Allied Cementing Pump Truck  
Pulled 2600' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Evers  
Well Plugging Supervisor

INVOICED

DATE 5-3-72

INV. NO. 5667-10