

KANSAS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED STATE CORPORATION COMMISSION JAN 8 1962 CONSERVATION DIVISION Wichita, Kansas

TO: Jewel M. Ogden, Director 500 Insurance Building 212 North Market Wichita 2, Kansas

1-4-62

File No. _____ County: Holmes Location: C NE SW Sec. 9 Twp. 13 Rge. 13 (E) (W) Name of Field: _____ Total Depth: 4688

I have this date completed supervision of plugging of:

Lease Name: Campbell "C" Well No. 1 Operator's Full Name: Pickrell Drilling Co. Complete Address: 405 4th Nat Bank Bldg, Wichita, Kas Plugging Contractor: Rt. Drilling Supply Co. Address: Hutchinson, Kas License No. 136 Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A ~~_____~~

Other well as hereafter indicated: _____ Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No If yes how long? _____ Reason: _____

Operation Completed: Hour 11 am Day 14 Month 12 Year 1961

The above well was plugged as follows:

278' of 8" surface casing - Hole was sealed to 4300' and 5 sacks cement dumped with dump bucket - Pulled 3780' of 5" casing - Mudded hole to 350' - Set rock bridge to 340' - Dumped 20 sacks cement on bridge - Mudded to 40' - Set rock bridge to 30' - Dumped cement to base of cellar -

Signed: [Signature] Conservation Division Agent

Reviewed: [Signature] Field Supervisor

Remarks:

INVOICED DATE 1-8-62 INV. NO. 4244-W