

KANSAS

AL

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities service Oil Co.

Complete Address Box 308, Great Bend, Kansas

Lease Name Hann "A" Well No. 1

Location SW NW NE Sec. 26 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4409'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated None

Plugging Contractor Glenn & Smith

Address Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:30 AM Day 3 Month 7 Year 1970

The above well was plugged as follows:

5/8" to 219' circulated w/ cement. 5 1/2" to 4393' cemented.

Open hole 4409' to 4393' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4300' Mud 4300' to 850'

Spotted 80 sacks cement 850' to 550' Mud 550' to 240'

Spotted 30 sacks cement 240' to 140' Mud 140' to 40'

Plug. Halls & 10 sacks cement 40' to 0'. Allied Pump Truck.

Pulled 2190' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward J. Jones
Well Plugging Supervisor

DATE 7/7/70

INV. NO. 2175-W