

KANSAS

KS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

7-7-70
RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Co.

Complete Address Box 308, Great Bend Kansas

Lease Name Hertel Well No. 1

Location C NE SW Sec. 26 Twp. 22 Rge. 22 ~~(E)~~ (W)

County Hodgeman Total Depth 4417'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated None

Plugging Contractor Glenn & Smith Pipe Pullers

Address Ellinwood, Kansas License No. 396

Operation Completed: Hour 10:00AM Day 3 Month 7 Year 1970

The above well was plugged as follows:

8 5/8" to 347' circulated w/ cement, 5 1/2" to 4409' cemented.

Open hole 4409' to 4417' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4350' Mud 4350' to 850'

Spotted 80 sacks cement 850' to 550' Mud 550' to 340'

Spotted 30 sacks cement 340' to 240' Mud 240' to 40'

Plug, Halls & 10 sacks cement 40' to 0'. Allied Pump Truck.

Pulled 3186' of 5 1/2" casing

I hereby certify that the above well was plugged as herein stated

INVOICED

Signed: *Edgar J. Eves*
Well Plugging Supervisor

DATE 7/7/70
INV. NO. 2176-W