

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dave Morgan Oil Company 15-185-61414-6000

Complete Address: Box 820, Blackwell, Oklahoma

Lease Name Roy Meyer Well No. # 1

Location NE NE NE Sec. 2 Twp. 23 Rge. 12 (E) (W) W

County Stafford Total Depth 3680

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Dave Morgan Drilling Company

Address: Box 820, Blackwell, Oklahoma License No. _____

Operation Completed: Hour 11:30AM Day 18th Month July Year 1964

The Above well was plugged as follows:

252' of 8 5/8" surface pipe, cemented with 225 sacks. Fluid level was
up in the hole. 1st cementing plug and 1/2 sack hulls was pushed in fluid
to 240', and cemented with 25 sacks, through the drill pipe. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged solid with
hulls on fluid at 40', and cemented with 10 sacks to base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/20/64

INV. NO. 9503-w

Signed: Archie Elving
Well Plugging Supervisor