

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 3 1964

12-3-64

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name E. H. Riggs 15-185-01031-0001

Complete Address: 1107 Union National Bldg., Wichita, Kansas

Lease Name Spangenberg Well No. # 1

Location SW SW NE Sec. 4 Twp. 23 Rge. 12 (E) (W) W

County Stafford Total Depth 3750

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 4:30PM Day 1st Month Dec. Year 1964

The Above well was plugged as follows:

244' of 8 5/8" surface pipe, cement circulated. 3739' of 5 1/2" long string,
cemented with 100 sacks. Plug back to 3578'. Top perforation 3449'. Plug
was pushed to 3430', 20' of sand, cemented with 5 sacks. Fluid level was
up in the hole. Bridge plug was set at 240', and 10' of rock bridge. 2
sacks of cement and 5% Calcium Chloride was mixed in barrel, and put on
plug at 230', through the dump bailer. And let set for 4 hours. Hole was
bailed dry, and 23 sacks of cement was added to the plug. Hole was filled
with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the
base of the cellar. 1814' of 5 1/2" long string was recovered from the hole.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/3/64

INV. NO. 294.11