

RECEIVED

AUG 29 2002

KCC WICHITA

8-29-02

FORM CP-1 (3/92)

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-22,464-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR L. D. Drilling Inc. KCC LICENSE # 6039  
(owner/company name) (operator's)

6/03

ADDRESS 7 SW 26th Ave CITY Great Bend

STATE Kansas ZIP CODE 67530 CONTACT PHONE # (620) 793-3051

LEASE IVY WELL# #1 SEC. 18 T. 22 R. 11 (East/West)

NE - SW - NW - SPOT LOCATION/OOOO COUNTY Stafford

3630 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

4290 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#

CONDUCTOR CASING SIZE  SET AT  CEMENTED WITH  SACKS

SURFACE CASING SIZE 8 5/8" SET AT 344' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 3636' CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: GIBB' - 3620'

ELEVATION 1831/ 1837 T.D. 3645' PBDT  ANHYDRITE DEPTH 580 (+1257)  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING pull pipe - plug as directed by KCC

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike Kasselmann PHONE# 620- 793-3051

ADDRESS 7 SW 26th Ave City/State Great Bend, KS 67530

PLUGGING CONTRACTOR Allied Cementing CO, INC KCC LICENSE #   
(company name) (contractor's)

ADDRESS 24 S Lincoln St Russell, KS 67665 PHONE # (785) 483-2627

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-28-02 AUTHORIZED OPERATOR (AGENT): Marilyn Davis

(signature)

Marilyn Davis

RECEIVED

AUG 29 2002

KCC WICHITA

DRILLERS WELL LOG

DATE COMMENCED: September 21, 1987  
 DATE COMPLETED: September 27, 1987

L. D. Drilling, Inc.  
 Ivy #1  
 NE SW NW Sec. 18-22-11  
 Stafford County, Ks.

Elevation: 1837 K.B.

0 - 493 Sand & Red Bed  
 493 - 1750 Shale-Lime streaks & rock  
 1750 - 2616 Lime & shale  
 2616 - 2794 Shale & lime  
 2794 - 3365 Lime & Shale  
 3365 - 3457 Lime  
 3457 - 3636 Lime & Shale  
 3636 - 3645 Arb.

FORMATION DATA

Anhy. (Top)	580	(+1257)
Anhy. (Base)	600	(+1237)
Heebner	3110	(-1274)
Toronto	3130	(-1294)
Douglas	3146	(-1310)
B. Lime	3243	(-1407)
Lans. K/C	3267	(-1431)
Base K/C	3496	(-1660)
Cong.	3516	(-1680)
Viola	3540	(-1704)
Simp.	3584	(-1748)
Arb.	3636	(-1800)

Surface Pipe: 8 5/8" new 20# @ 344'  
 with 250 sx. 50/50 posmix, 2% gel,  
 3% CC.

Production Csg. 5 1/2" set @ 3636 with  
 125 sx. 50/50 1/2 pzmix, 18% salt .75 CFR2  
 20 bbl salt flush.

A F F I D A V I T


STATE OF KANSAS      SS  
 COUNTY OF BARTON

Greg Davidson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson  
 Greg Davidson

Subscribed and sworn to before me this 22nd day of October, 1987

Bessie M. DeWerff  
 Notary Public: Bessie M. DeWerff





## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

L.D. Drilling, Inc.  
RR 1 Box 183B  
West 10th Street  
Great Bend, KS 67530-9801

August 30, 2002

Re: IVY #1  
API 15-185-22464-00-00  
CNESWNW 18-22S-11W, 3630 FSL 4290 FEL  
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams  
Production Supervisor