

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply, Inc.
Complete Address Box 169, Russell, Kansas 67665
Lease Name Miller Estate Well No. 4
Location C NE NE Sec. 8 Twp. 22 Rge. 22 ~~W~~ (W)
County Hodgeman Total Depth 4575'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Glenn Casing Pulling Co.
Address Ellinwood, Kansas License No. 396
Operation Completed: Hour 12:30Pm Day 23 Month 6 Year 1973

The above well was plugged as follows:

8 5/8" to 260' circulated w/ cement. 5 1/2" to 4574' cemented.
Top perforations 4480'. Plug bottom w/ sand & 5 sacks cement.
Top of cement 4080' Mud 4080' to 800'
Spotted 80 sacks cement 800' to 500' Mud 500' to 250'
Spotted 30 sacks cement 250' to 150' Mud 150' to 40'
Plug, Hulls ^o 10 sacks cement 40' to 00' Company Pump
Pulled 2525' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

DATE 6/28/73

INV. NO. 7561-W

Signed: Edward J. Evers
Well Plugging Supervisor