

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

*Rec'd 10-7-82*

API Number 15-083-20, 998-0000 *R*

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name High Plains Oil Exploration

Complete Address 25th. & Vine, Hays, Ks 67601 # 6171

Lease Name Cure Well No. 1

Location C-NE SE Sec. 23 Twp. 22 Rge. 21 (East) (West)

County Hodgman Total Depth 4635'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations

Address P.O. Box 506, Russell, Ks. 67665 License No. 627

Operation Completed: Hour: 12:00 PM Day: 26 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 367' S.P. cas. w/ 200 sacks common - 2% Gel, 3% Cal. U.

Ordered 160 sacks 50% permix - 4% Gel - 3% Cal. U. + 8 5/8" plug.

Spot w/ drill stem w/ heavy mud between all plugs.

1st plug @ 990' w/ 100 sacks.

2nd plug @ 400' w/ 40 sacks.

3rd plug - solid ledge of shells + plug @ 40' w/ 10 sacks.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 367' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Signed: \_\_\_\_\_  
Conservation Division Agent

**INVOICED**  
DATE 10-18-82  
INV. NO. 1401-W