

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

March, 23, 1968

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bea Drilling Co., Inc.

Complete Address: Box 247 Ellinwood, Kansas.

Lease Name Darr Well No. #1

Location SW-SW-SW Sec. 18 Twp. 22 Rge. 11W (E) (W) W

County Stafford Total Depth 3665'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Pipe Pulling Co.

Address: 204 East 6th. Ellinwood, Kansas. License No. 396

Operation Completed: Hour 12: N Day 22 Month March Year 1968

The Above well was plugged as follows:

267 ft. of 8 5/8" surface pipe., circulated with 165 sacks cement. 4 1/2"
long string set at 3657. Rock from 3110 ft. to 3096, dumped 3 sacks
cement. Set plug at 2895 & 2 sacks cement. Squeezed hole in casing
at 267 ft. Drilled out cement to 400 ft. Pumped 10 sacks mud & 40 sacks
cement at 600 lbs. pressure. Cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *Hummer Justus*
Well Plugging Supervisor

INVOICED

DATE 3/26/68

INV. NO. 7465-W